

SAMPLE SUMMARY OF QUANTITIES

QUANTITIES ARE APPROXIMATE ONLY
CONTRACTOR SHALL VERIFY ALL QUANTITIES TO HIS/HER SATISFACTION

ITEM	QUANTITY	UNITS
EXCAVATION	NOT DETERMINED	
EMBANKMENT	NOT DETERMINED	
SAW CUT	569	LF
2" ASPHALT CONCRETE PAVEMENT CLASS B (ROADWAY)	128	TON
2" CRUSHED SURFACING TOP COURSE (ROADWAY)	69	CY
6" GRAVEL BASE (ROADWAY)	215	CY
2" ASPHALT CONCRETE PAVEMENT CLASS B (PATH)	19	TON
2" CRUSHED SURFACING TOP COURSE (PATH)	10	CY
6" GRAVEL BASE (PATH)	32	CY
2" WIDE ROLLED CONCRETE CURB	959	LF
CONCRETE CURB (ENTRANCE)	86	LF
CATCH BASIN, WSDOT TYPE 1	2	EA
6" PVC STORM DRAIN	33	LF
6" ADS STORM DRAIN (INFILTRATION TRENCH)	33	LF
SANITARY SEWER MANHOLE	10	EA
8" SANITARY SEWER (38 LATERALS)	695	LF
12" SANITARY SEWER	699	LF
FIRE HYDRANT ASSEMBLY	2	EA
8" WATER LINE	586	LF
12" WATER LINE	516	LF
8" GATE VALVE	2	EA
WATER SERVICE CONNECTION (DOUBLE)	7	EA
WATER SERVICE CONNECTIONS	7	EA
STOP SIGN	2	EA

SAMPLE